

ATTACHMENT A

Project Number: RFB 17BCP04J

County: Bastrop

Highway: County Line Road, ETC.

BASIS OF ESTIMATE: TREE TRIMMING

MAP GRID #	COUNTY ROAD NAME	APPRX. LIMITS FROM	APPRX. LIMITS TO	LENGTH (MI)
E1, E2	County Line Rd	Old San Antonio Rd	Rianna Woods Dr	1.70
F2	Hill Rd	FM 672	End of Hill Rd	0.91
D1	Jacobson Rd	Travis County Line	Mesa Dr	0.75
D3	Lake View Dr	Marjess Dr	End of Lake View Dr	1.38
D3	East McDonald Ln	SH 21	End of East McDonald Ln	0.60
D1, D2	Mesa Dr	FM 2430	End of Mesa Dr	2.60
E2	Mesquite Dr	Watts Ln	End of Mesquite Dr	2.77
D2	Mustang Crossing	Heritage Oaks Dr	End of Mustang Crossing	0.17
E1, E2	Old San Antonio Rd	FM 812	Caldwell County Line	3.82
E3	Pleasant Chapel Rd	FM 535	FM 20	1.64
F3, F4	Sand Hills Rd	Goertz Dr	Red Rock Ranch Rd	3.50
D2	Shady Oaks Loop	Thousand Oaks Dr	End of Shady Oaks Loop	1.35
D2, E2	Watts Ln	SH 21	FM 812	2.91
E4, E5	Glass Ln	Watterson Rd	End of Glass Ln	2.00
			Total	26.10

GENERAL:

This contract shall commence upon the issuance of a Notice to Proceed by the Bastrop County Commissioner or his/her designee. The working days listed below shall rule for the completion of the work.

The Contractor will be given written notice to begin work on this project. Work must begin within ten (10) calendar days after such notification. Time charges will begin when work begins regardless if it falls within ten (10) calendar days of the notification to begin work. The Contractor shall have Ninety (90) **CALENDAR** days to complete the work.

Prior to bidding, contractor **SHALL** conduct a visual inspection of all roadways requiring work under this contract, in order to become familiar with the scope and the limits, and to anticipate the quantity of work required.

A minimum of a 48 hour notice shall be given to the Bastrop County Commissioner or his/her designee prior to commencing the work under this contract.

All construction equipment that is used in roadway work must be outfitted with highly visible omnidirectional flashing warning lights.

All locations used for storing construction equipment, materials, and stockpiles of any type, within the right of way, will be as directed. Use of right of way for these purposes will be restricted to those locations where driver sight distance to businesses and side street intersections is not obstructed and at other locations where an unsightly appearance will not exist. The Contractor will not have exclusive use of right of way but will cooperate in the use of the right of way with the County and various public utility companies as required.

Project Number: RFB 17BCP04J

County: Bastrop

Highway: County Line Road, ETC.

Protect all areas of the right of way, which are not included in the actual limits of the proposed construction areas, from disturbance. Restore any area disturbed because of the Contractor's operations to a condition as good as, or better than, before the beginning of work at no cost to the County.

Immediately repair any damage that occurs to existing fences or private property as a result of the Contractor's operation to a condition that is as good as, or better than before beginning of work.

PROSECUTION AND PROGRESS

Working days will be charged in accordance with Standard Work Week. Work hours will be between 8:00 a.m. and 4:30 p.m. unless otherwise approved.

A minimum of a 48 hour notice shall be given to the Bastrop County Commissioner or his/her designee prior to commencing the work under this contract. Any work performed without authorization will not be eligible for payment.

BARRICADES, SIGNS, AND TRAFFIC HANDLING

The Traffic Control Plan (TCP) for this project shall be as shown in the plans, as detailed on standard plan sheets BC (1) thru BC (12)-14, and as provided for in Part VI of the Texas Manual on Uniform Traffic Control Devices. The Contractor shall provide within the limits of the project, standard barricades, warning signs, delineators, lights, cones, and flaggers in sufficient numbers and any combination as considered necessary by the Bastrop County Commissioner or his/her designee. Contractor shall be solely responsible for maintain safety at all work sites. Contractor shall take all reasonable steps to insure safety for both workers and visitors to the site(s) to include traffic control. Contractor will also be solely responsible to ensure that all OSHA requirements are met and a safety officer is assigned to the project for the duration of this project.

**The attached TXDOT Standards shall be adhered to by the CONTRACTOR and all approvals shall be made by the Bastrop County Commissioner or his/her designee.

All roads within this project area shall remain in a condition suitable for cars to pass through at all times.

Approval by the Bastrop County Commissioner or his/her designee is required prior to any lane closures.

The work performed in accordance with this Item shall be incidental to the cost of the work; including all equipment, mobilization, traffic control, labor, tools, and incidentals needed to complete this work.

Project Number: RFB 17BCP04J

County: Bastrop

Highway: County Line Road, ETC.

TREE TRIMMING

Complete all work on a roadway before starting operations on another roadway, unless approved. Complete tree trimming operations on one side of the roadway before beginning operations on the other side.

Limits of tree trimming will include the complete width of the right of way.

The tree trimming limits shown include the left and right sides of each roadway.

Minimum height for tree trimming is 14 feet vertically from existing ground/roadway.

Contractor will avoid trimming all oak trees within the project limits as to limit the potential spread of any possible Oak Wilt disease.

Burning of brush and/or vegetative debris will NOT be permitted. Cleanup of debris will be continuously and concurrently with the tree trimming operation.

All driveways, walkways, paths, right of ways and road ways will be left clean at the end of each day.